

Prefabricated Concrete Building Solutions

Call 205-980-4565 Fax 877-675-5851 ModularConnections.com

> STORM SHELTERS

Modular Connections' Storm Shelters Feature:

- FEMA 361 & 320 Ratings
- 250MPH Wind Load / Seismic Zone 4
- ADA Accessible
- Built to Order per Occupancy of 5ft² / Occupant
- Pre-Engineered Plans and Specs
- Above-Ground Installation
- Pre-Installed HVAC / Electrical / Plumbing



Tornado Shelter—FEMA 361 Rated

> COMMUNICATIONS

Modular Connections' Communication Shelters Feature:

- Pre-Installed HVAC & Electrical
- Custom Sizing and Entry Ports
- Cable Tray, Racks & Drop-Downs
- Clean, Finished Interiors with 3/4" FRP Laminated Plywood Walls for Extra Strength
- Level 4 Bulletproof Walls
- Custom Grounding



Communications Equipment Shelter

Let Modular Connections be your new source for the latest in above ground tornado shelters and communication equipment shelters for your community. Our experienced team can take you from design to final installation to further secure and modernize your community.

CCR
Registered

MODULAR CONNECTIONS, LLC
CONNECTING YOU TO THE BEST BUILDING SOLUTIONS

Small
Business



205-980-4565 Fax 877-675-5851
1090 Industrial Blvd, Bessemer, AL 35022
www.ModularConnections.com Sales@ModularConnections.com



Quote Request Fax

For a free quote, please print, fill out and fax back to 877-675-5851.

Company or Organization: _____ Contact Name: _____ Phone: () _____	Fax: () _____ Email: _____ Address: _____ _____ _____
---	--

> STORM SHELTERS

Occupancy Requirements:

<input type="checkbox"/> Less than 16	<input type="checkbox"/> 100
<input type="checkbox"/> 25	<input type="checkbox"/> 150
<input type="checkbox"/> 50	<input type="checkbox"/> 200
<input type="checkbox"/> 75	<input type="checkbox"/> Other (_____)

Exterior Finishes:

Texture Paint (standard) Color _____

Simulated Brick Simulated Block

HVAC:

Passive Ventilation

Mechanical Ventilation

A/C

Heat

Dehumidification System

Interior Options:

Unisex ADA Restroom

Men's & Women's ADA Restrooms

Storage Closet

Emergency Generator System

Fixed Seating (10" Benches)

Insulation & Interior Finishing

Vinyl Tile Flooring with Base Molding

Accessories (Recommended by FEMA 361):

NOAA Weather Radio

Wall Mounted Fire Extinguisher

Duplex Receptacles (Qty _____)

Emergency Lighting with Battery Backup

Flashlights with Continuously Charging Batteries

Air Horn

Fixed Storage Cabinet with Charging Center

Logistics and Site Work:

Shelter and Delivery Quote

Shelter, Delivery and Offloading Quote

Shelter, Delivery, Offloading and Site Work Quote

> COMMUNICATIONS

Dimensions:

Length _____' Width _____' Interior Height _____'

Rooms:

One Two Generator Room

HVAC:

Single Dual

1 Ton 2 Ton 3 Ton 4 Ton 5 Ton

Access:

3' x 7' 18 Gauge Steel Door (Qty _____)

6' x 7' 18 Gauge Steel Double Doors (Qty _____)

Electrical System:

_____ AMP _____ Phase _____ Volt

Includes:

Load Center, Main Breaker, Main Lugs Only

Duplex Outlets every 4' on Three Walls, (1) Exterior GFCI Outlet (1) Exterior 70W HPS Light Fixture w/ Photocell, 4' Dual Bulb Fluorescent Lights as required with Switch

Entry Ports:

Microflex 4" X _____ Ports

Other _____

PVC Telco Port 2" 3" 4"

Generator with Automatic Transfer Switch:

Onan Kohler Generac _____

Cable Ladder:

12" 18" 24" Qty. _____ Ft.

Grounding:

R-56

Halo #2AWG #2/0 Other

Halo Drop Qty _____ / _____ #2T Other

Equipment Drop Qty _____ / _____ #2AWG #6AWG

Cable Ladder Ground Jumpers

Copper Ground Bar with Ground Drop

Surge Arrestors:

AC Data

Other _____

(Additional options available, please call for more info.)